BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT42442

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/02/2020-21, Date: 28.05.2020

Name of Work:Improvements to roads and footpath maintenance in ward no 11 (Kuvempunagara)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Deepak B ( )	
				In Figures	In Words
1	81.9	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	210.2	Rupees Two Hundred Ten and Twenty Paise Only
2	328.05	Removing and refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	93.49	Rupees Ninety Three and Forty Nine Paise Only
3	76.95	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	623.28	Rupees Six Hundred Twenty Three and Twenty Eight Paise Only
4	1.62	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4542.82	Rupees Four Thousand Five Hundred Forty Two and Eighty Two Paise Only
5	6.48	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4882.06	Rupees Four Thousand Eight Hundred Eighty Two and Six Paise Only
6	10.8	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	126.44	Rupees One Hundred Twenty Six and Forty Four Paise Only
7	400	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	822.73	Rupees Eight Hundred Twenty Two and Seventy Three Paise Only
8	22.7	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4827.75	Rupees Four Thousand Eight Hundred Twenty Seven and Seventy Five Paise Only
9	450	Providing precast slab of 100 mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge- Data rate	Sqm	1963.08	Rupees One Thousand Nine Hundred Sixty
10	9	Providing precast slab of 250 mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge- Data rate	Sqm	4551.12	Rupees Four Thousand Five Hundred Fifty One

Signature of the Contractor

10/09

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92